


Stone Crafters LLC
6084 Reega Ave Egg Harbor Twp NJ 08234
Phone: (609)646-0406 Fax: (609)646-9011
www.stonecrafters-nj.com info@stonecraftersnj.com



REMOVAL & REPLACEMENT of EXISTING COUNTERTOP SIGN-OFF

TEMPLATE OVER EXISTING COUNTERTOP

There are several options for templating over top of an existing countertop.

- Templating for a new Counter Top in most cases can be done with the existing counter top & backsplash, sink & cooktop being left in place. However, sometime items need to be removed in order to do the template properly. The StoneCrafters templater will inform you of items that will need to be removed in order to do the template. The templater will also inform your Project Manager at StoneCrafters of items that need to be removed. The Project Manager will advise you of the options available to you in order to complete the template.
- In most cases the new Granite or Quartz counter tops will be thinner than the existing counter tops. There will be areas where the new counter tops will not cover voids on the walls, against wood trim or existing backsplash left by the removal of the existing counter tops that will need to be painted or trimmed out with new wood trim. StoneCrafters will Not perform this work.
- There are issues that may arise after the removal of the existing counter tops that is not apparent until the removal of the existing counter tops such as:
 - Cabinets not sufficient to support the new counter tops without modifications.
 - Unlevel Cabinet not able to support the new counter tops without shimming support that will require additional wood trim work to cover the space left by shimming.
 - Additional wall ledgers or built in support to support the new counter tops.

There are some items that StoneCrafters can offer at an ADDITIONAL COST to cover spaces or voids caused during the new counter top installation.

- Build Up Strips
- Backsplash to cover gaps between the new counter tops and existing Wall conditions.
- Sanded Tile Caulk for Existing Tile Backsplash where the Backsplash meets new counter tops
- Cabinet Adjustments & Minor Wood Trim Work
- Plumbing disconnect and reconnect
- Painting touch up
- Cleaning Services

REMOVAL of EXISTING COUNTER TOPS

- The removal of the existing counter tops will most likely happen the day of the installation of the new counter tops. However , we may recommend to remove the existing counter tops prior to the new counters being installed to inspect existing cabinets or for a proper measurement.
- The time frame to remove existing counter tops and install new will vary depending on the existing counter top condition and the items that we need to deal with to get the existing counter tops out and the new tops in. The removal and installation could take 4 hours to 2 days.

INSTALLATION of NEW COUNTERTOPS WHEN EXISTING HAS BEEN REMOVED

- We strongly recommend that all of the contents of the cabinets be removed prior to removal of the existing tops as there will be debris from the existing counter tops that will fall down into the cabinets during the removal. The final clean up of the cabinets will not be done by StoneCrafters.

- Care will be taken during the installation of the new counter tops. However, scrapes, punctures or marks to wall surfaces are possible. These items are considered incidental and are the homeowners responsibility to repair.

- Every effort will be made to fit the new stone counter tops as close as possible to walls and cabinet panels. However, it is not always possible. There may be additional trim, caulk or grouting required. This is not the responsibility of StoneCrafters unless agreed to by StoneCrafters.

The final decision on which options are best depends upon job site conditions and is typically decided by a Stone Crafters representative at the time of template. To achieve the best fit and a successful template and install of the new stone or quartz countertops, Stone Crafters may be required to change the preferred option once the job site has been assessed. At that time, additional work may be required by the homeowner or StoneCrafters before a template and/or installation can be completed.

Signature: _____ Date: _____